

SLIPLINING/SEWER REHAB

Henrico County, Virginia 72" Sanitary Sewer Rehab

Owner: County of Henrico, Virginia

Project Manager: K. Michael Hall, CEO PROJECT SUPERINTENDENT: Mike Crenshaw FOREMAN: Kerry Decker

WHAT WE DID: Cleaned, televised and sliplined 1800 LF of existing 72" PCCP sanitary sewer with 66" flush wall HOBAS Fiberglass Pipe. Grouted annulus with lightweight grout and installed two new manholes, then post televised the completed line. Flow was running continuously and at a very high velocity, but no bypassing was required, as is typical with the slipline method of rehabilitation.

CONTRACT AMOUNT: \$1,237,200



Lowering 66"



Unstrapping 66"



Setting push head



Slipping 66"